Radon Test Report Armstrong Elementary 8855 Inwood Ave S, Cottage Grove, MN 55016 Meridian Consulting Group

Radon testing was conducted at Armstrong Elementary by a licensed radon measurement professional following ANSI/AARST's 'Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings' standards. Quality control measurements including duplicates and blanks were conducted at their required quantity.

Test Duration: 48 hours Start Date: 03/15/2023 End Date: 03/17/2023

Licensed Radon Measurement Professional: Wendy German, RMEA-00447 Meridian Consulting Group 320-224-1908 wendy@meridianconsult.net

Laboratory: AirChek, NRPP Certified Lab #101138 AL

Device: AirChek ProChek

Result Summary:

51 rooms were tested. No test results are at or above the EPA action level of 4 pCi/L. Two test results were at least half of the action level, between 2 pCi/L and 4 pCi/L.

Recommendations:

Retest every five years. Also retest if any of the following conditions occur:

- A new addition is constructed or alterations for building rehab or reconfiguration occur;
- A ground contact area not previously tested is occupied;
- Heating and cooling systems are significantly altered;
- Ventilation is significantly altered by extensive weatherization, changes to mechanical systems or comparable procedures;
- Significant soil openings occur due to alterations to sumps or drain tiles, cracks in slabs or walls; earthquakes; construction blasting nearby; or any other soil opening created in or adjacent to the building; or
- A mitigation system is installed, altered, or repaired.

More information about radon is available by contacting the Minnesota Department of Public Health at:

Phone: 651-201-4601 Website: MN.gov/radon Email: health.indoorair@state.mn.us

Conditions Observed During Testing

The required conditions were observed at deployment and retrieval: Yes

If no, describe: N/A

Interior building temperature was between 65 and 80 degrees: Yes

Testing devices were tampered with during the test: No

If the building has a mitigation system, it was operation: N/A

Unusually high winds or storm during test: No

HVAC operating normal during test: Yes

Construction activity in or adjacent to building: No

Any other factors that could have influenced results: No

Test Checklist

The locations of the detectors were selected so that they were less likely to be disturbed during testing: Yes

The detectors were not placed in an area of high humidity: bathrooms, laundry rooms, sump areas, etc: Yes

The detectors were not located near drafts caused by HVAC vents, windows, and doors: Yes

The detectors were not placed near areas of excessive heat, such and radiators, appliances, or in direct sunlight: Yes

The detectors were not placed within 1 foot of outside walls or within 3 feet of exterior doors or windows: Yes

RADON TESTING RESULT REPORT FOR: **ARMSTRONG ELEMENTARY** - Test Conducted 3/15/23 to 3/17/23

Result	Туре	Location	Sample ID
1.4	Standard	B1	11653054
1.0	Standard	B2	11653053
0.8	Standard	В3	11653052
1.0	Duplicates	B4	11653050/11653051
1.5	Standard	B5	11653049
1.0	Standard	В6	11653041
1.0	Standard	B6A	11653042
0.7	Standard	B6B	11653043
0.7	Standard	B6C	11653044
0.9	Duplicates	B7	11653046/11653045
0.8	Standard	Cateteria	11653023
0.6	Standard	Computer Lab	11653014
1.0	Standard	Conference Room	11653004
0.8	Standard	G1	11653022
1.0	Standard	G2	11653021
0.9	Standard	G3	11653020
0.6	Standard	G4	11653019
0.7	Duplicates	G5	11653016/11653017
1.4	Standard	G6	11653018
0.7	Standard	Gym 1	11653024
<.3	Standard	Gym 2	11653025
1.5	Standard	Health Office	11653005
0.9	Standard	KA	11653048
1.1	Standard	КВ	11653047
0.7	Standard	Kitchen	11653028
<.3	Standard	Library 1	11653055
0.8	Standard	Library 2	11653056
1.0	Standard	Main Office	11653001
0.8	Standard	Media Office	11653057
0.7	Standard	Music	11653030
0.8	Standard	Music Office	11653031
2.0	Standard	Principals Office	11653003
1.0	Duplicates	R1	11653007/11653008
1.3	Standard	R2	11653009
1.1	Standard	R3	11653010
1.5	Standard	R4	11653011
1.2	Standard	R5	11653013
1.5	Standard	R6	11653012
<.3	Standard	Receiving	11653029
0.5	Standard	Staff Lounge	11653026
0.9	Standard	Workroom	11653006
0.8	Duplicates	Y1	11653033/11653032
0.8	Standard	Y2	11653034

RADON TESTING RESULT REPORT FOR:

ARMSTRONG ELEMENTARY - Test Conducted 3/15/23 to 3/17/23

11653035	Y3	Standard	0.5
11653036	Y4	Standard	1.1
11653040	Y5	Standard	0.9
11653039	Y6	Standard	<.3
11653038	Y7	Standard	0.8
11653037	Y8	Standard	2.1

Quality Assurance Field Blanks

11653002	Main Office	Field Blank	<.3
11653015	Computer Lab	Field Blank	<.3
11653027	Staff Lounge	Field Blank	<.3